

# PROJECT SCHEDULE

## Contents

### TENDER ISSUE

k20.AU PTY. LTD.  
t/a k20 ARCHITECTURE  
325 COVENTRY STREET  
SOUTH MELBOURNE 3205  
VICTORIA AUSTRALIA  
www.k20au.com  
t: 9699 4440  
f: 9699 5550  
e: melboffice@k20au.com



<b>Project No:</b>	_0335.00
<b>Project Name:</b>	MARIBYRNONG RIVER CHILDCARE REDEVELOPMENT
<b>Project Address:</b>	6 WESTS ROAD, MARIBYRNONG

Schedule Number	Schedule List	Revision	Issue Date
A-SC.01	External Finishes	T02	07-July-2015
A-SC.02	Floor Finishes	T02	07-July-2015
A-SC.03	Internal Wall Finishes	T02	07-July-2015
A-SC.04	Ceiling & Soffit Finishes	T02	07-July-2015
A-SC.05	Door and Window Finishes	T02	07-July-2015
A-SC.06	Joinery	T02	07-July-2015
A-SC.07	Fixtures & Fittings	T02	07-July-2015
A-SC.07	Electric & Equipment	T02	07-July-2015
A-SC.09	Specialist Equipment	T02	07-July-2015

#### IMPORTANT NOTE


All project schedules are to be read and co-ordinated with all other contract documents including project specifications prior commencement of any works, pricing, ordering and any other associated work. Any discrepancies are to be reported to the Superintendent for clarification. The Builder is to allow to supply and install all items within these schedules. For any item(s) noted in the project Drawings or Documentation which are not specifically indicated in the Project Schedules, the Builder is to provide for a commercial grade quality item to suit the documented item and provide a sample to the Superintendent for approval.

# PROJECT SCHEDULE

## External Finishes

### TENDER ISSUE

k20.AU PTY. LTD.  
t/a K20 ARCHITECTURE  
325 COVENTRY STREET  
SOUTH MELBOURNE 3205  
VICTORIA AUSTRALIA  
www.k20au.com  
t: 9699 4440  
f: 9699 5550  
e: melboffice@k20au.com



#### IMPORTANT NOTE

All project schedules are to be read and co-ordinated with all other contract documents including project specifications prior commencement of any works, pricing, ordering and any other associated work. Any discrepancies are to be reported to the Superintendent for clarification. The Builder is to allow to supply and install all items within these schedules. For any item(s) noted in the project Drawings or Documentation which are not specifically indicated in the Project Schedules, the Builder is to provide for a commercial grade quality item to suit the documented item and provide a sample to the Superintendent for approval.

MARIBYRNONG RIVER CHILDCARE





**Project Name:** REDEVELOPMENT




**Project Number:** \_0335.00



**Schedule No. A-SC.01**

**Issue Date:** 07-July-2015

**Revision:** T02

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	ESD / Special Notes
1	PF-01	Paint finish to window frame/display box/feature batten	Dulux		Dulux Antique White U.S.A.	Dulux		
2	PF-03	Paint finish to external walls	Dulux		Dulux Hog Bristle	Dulux		
3	PF-04	Paint finish to fascia	Dulux		Dulux Hog Bristle	Dulux		
4	PF-05	Paint finish to window frame/display box/feature batten	Dulux		Dulux Tuscan Image A74	Dulux		

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	ESD / Special Notes
5	PF-06	Paint finish to window frame/display box/feature batten	Dulux		Dulux Rainforest Glow A230	Dulux		
6	PF-07	Paint finish to window frame/display box/feature batten	Dulux		Dulux Golden Koi A134	Dulux		
7	PF-08	Paint finish to window frame/display box/feature batten	Dulux		Dulux Wing Commander A338	Dulux		
8	GU-01	Eave Gutter	Colour to match PF-04					
9	CF	Cap Flashing	Colour to match PF-04					
10	Refer to note on elevations	New Aluminium Signage on Roof Fascia & New Signage near existing Gas Meter						
11	DP	Downpipes	Colour to match PF-04					

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	ESD / Special Notes
12	Refer to note on site plan	New safety fence	Flat Top- Enden - Steel Panel 1.5mH x 2.4mW, Gate 1.5mH x 3mW		Powdercoat Black Steel	<a href="http://www.arcfences.com.au/residential-fencing/aluminium-fencing/flat-top-eden/">http://www.arcfences.com.au/residential-fencing/aluminium-fencing/flat-top-eden/</a>	Outdoor play areas & near existing gate meter	Gate to have magnetic latch, concrete footings for posts
13	Refer to note on elevations	Powder coated Steel 100x50 RHS	Steel		To match Colorbond Monument	Cossett	Entry Canopy	
14	Refer to note on elevations	Paint Finish Aluminium Strips 100X50	Aluminium RHS posts		Refer to Architectural Documentation for colour details	Cossett	External Facades	
15	RF-01	Colorbond Roof Finish	Lysaght Colorbond Roofing		Klip-Iok / Spandek Surfmist	Colorbond	New Roofs & Playroom 5 Canopy	Confirm if water run off to new/existing water tank units
16	RF-02	Fibre Glass Roof Finish to Entry Canopy profile to match colorbond roof				Ampelite	Semi-Transparent section of the Entry Canopy	
17	WT-03	Lexan Thermoclick 40mm to External Facades	Lexan Thermoclick Opal 40mm		Opal	Ampelite	Façade	
18	EJ	Concrete Expansion Joints						
19	TM-01	Ironbark for external feature battens at entry area	Recycled Timber 75X50			Timber Revival		
20	TM-02	Black Butt for external seating at entry area	Recycled Timber 65x42, 150x42			Timber Revival		

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	ESD / Special Notes
21	CON	External Concrete					Entry, Bike Racks, under covered area to Playroom 5	Natural, non-slip broom finish
22	refer to note on elevations	External fixed louver screen	55mm elliptical louvre blade @ 50mm centres			Metalart	Playroom 5	
23		Roof platform for roof mounted mechanical units	Con-form platform			Con-form Group	Underneath roof mounted mechanical units	

# PROJECT SCHEDULE

## Floor Finishes

### TENDER ISSUE

k20.AU PTY. LTD.  
t/a k20 ARCHITECTURE  
325 COVENTRY STREET  
SOUTH MELBOURNE 3205  
VICTORIA AUSTRALIA  
www.k20au.com  
t: 9699 4440  
f: 9699 5550  
e: melboffice@k20au.com



MARIBYRNONG RIVER CHILDCARE

**Project Name:** REDEVELOPMENT

**Project Number:** \_0335.00

**Schedule No. A-SC.02**



**Issue Date:** 07-July-2015



**Revision:** T02

#### IMPORTANT NOTE

All project schedules are to be read and co-ordinated with all other contract documents including project specifications prior commencement of any works, pricing, ordering and any other associated work. Any discrepancies are to be reported to the Superintendent for clarification. The Builder is to allow to supply and install all items within these schedules. For any item(s) noted in the project Drawings or Documentation which are not specifically indicated in the Project Schedules, the Builder is to provide for a commercial grade quality item to suit the documented item and provide a sample to the Superintendent for approval.

- A) Refer to specification & contract documentation for floor cover plates & transition trims between different floor finishes. If none is specified Builder is to allow for in the contract price the cost to supply and install a Raven manufactured cover plate suitable for the transition. All to the Architects approval prior ordering and installation.
- B) Where floor finishes changes between rooms, change is to terminate at center line of door leaf in closed position.
- C) All floor surface gradient and fall are to be constructed in accordance with contract documentation and specification. All falls to floor waste are to be bucket tested to ensure sufficient fall is achieved for surface drainage.
- D) Where applicable provide suitable connecting profile to all junctions between floor vinyl and vinyl wall junction.
- E) Builder is to confirm all floor substrate and structure are prepared to the industry best practice and in accordance with floor finishes manufactureres recommendation and detail prior installation.

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	ESD/Special Notes
1	VIN-01	Vinyl floor finish to non-wet areas	Vinyl floor		Boa Vista	Gerflor	Playroom 5, Playroom 6	<b>Contractor to note Boa Vista has 10-12 lead time period.</b>
2	VIN-02	Vinyl floor finish to wet areas, airlock & entry	Vinyl floor		Tarasafe ultra Non Sip Pebble	Gerflor	Entry Airlock, Foyer, Wet areas, MCH 01, 02	Remove existing floor finishes to Playroom 6 Children's WC & make good to prepare for floor finishes

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	ESD/Special Notes
3	CAR-01	MCH & Playrooms Carpet Tile Floor Finish generally	Carpet floor tiles		Cubic - Construction	Interface flooring	MCH Waiting, MCH 01, MCH 02	
4	MAT	Recessed entry floor mat	DOOR MAT		TUFF SCRAPE CHARCOAL	BIRRUS MATTING		Allow for slab set down
5	COV	Coved Skirting to Vinyl Floor Areas			To match Vinyl Floor Colour			
6	SK	Skirting to Carpet Tile Areas			To match paint finish colour to walls			

# PROJECT SCHEDULE

## Internal Wall Finishes

### TENDER ISSUE

k20.AU PTY. LTD.  
t/a k20 ARCHITECTURE  
325 COVENTRY STREET  
SOUTH MELBOURNE 3205  
VICTORIA AUSTRALIA  
www.k20au.com  
t: 9699 4440  
f: 9699 5550  
e: melboffice@k20au.com



#### IMPORTANT NOTE

All project schedules are to be read and co-ordinated with all other contract documents including project specifications prior commencement of any works, pricing, ordering and any other associated work. Any discrepancies are to be reported to the Superintendent for clarification. The Builder is to allow to supply and install all items within these schedules. For any item(s) noted in the project Drawings or Documentation which are not specifically indicated in the Project Schedules, the Builder is to provide for a commercial grade quality item to suit the documented item and provide a sample to the Superintendent for approval.

MARIBYRNONG RIVER CHILDCARE

**Project Name:** REDEVELOPMENT




**Project Number:** \_0335.00

**Schedule No. A-SC.03**



**Issue Date:** 07-July-2015

**Revision:** T02

- A) Wall linings/junctions/punctuations are to be fully air tight seal throughout.
- B) Allow to patch and paint throughout where new works adjoins existing.
- C) Provide water proofing in accordance with BCA and specification.
- D) Provide Skirting and ceiling cornice as per specification. If none specified builder is to allow for in the contract price the supply and installation of 100mm X19mm KDHW rectangular profile skirting with painted finish & square set finish to ceiling cornice with painted finish.
- E) All painted wall surface are to be sealed and primed as per specification prior to carrying out finishes coat. A test sample surface area of 1.0sqm are to be conducted on site and presented to the Principal's approval prior carryout all painting works.
- G) Refer to architectural drawings for any tile set-out.

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	Special Notes
1	PA	Children's WC Partitions	Compact Laminate		Compact Laminate Olive	Laminex	Playroom 5 & 6 Chilren's WC	
2	VIN-03	Internal wall vinyl finish	Wall Vinyl		Mushroom	Armstrong Wallflex	Wet areas & behind handwash basins	
3	SB	Slashback	National Tiles		BELWP312 Café Taupe Gloss 300x00	National Tiles	Behind sinks	



Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	Special Notes
4	PF-01	Internal walls paint finish generally	Dulux		Antique White			
5	WF-01	Acoustic panel/pin board	Autex Sanz				MCH 01, 02 & MCH Waiting	
6	WF-02	Acoustic panel/pin board	Autex Wasabi				Playrooms	

# PROJECT SCHEDULE

## Ceiling & Soffit Finishes

**TENDER ISSUE**

k20.AU PTY. LTD.  
t/a k20 ARCHITECTURE  
325 COVENTRY STREET  
SOUTH MELBOURNE 3205  
VICTORIA AUSTRALIA  
www.k20au.com  
t: 9699 4440  
f: 9699 5550  
e: melboffice@k20au.com



### IMPORTANT NOTE

All project schedules are to be read and co-ordinated with all other contract documents including project specifications prior commencement of any works, pricing, ordering and any other associated work. Any discrepancies are to be reported to the Superintendent for clarification. The Builder is to allow to supply and install all items within these schedules. For any item(s) noted in the project Drawings or Documentation which are not specifically indicated in the Project Schedules, the Builder is to provide for a commercial grade quality item to suit the documented item and provide a sample to the Superintendent for approval.

MARIBYRNONG RIVER CHILDCARE

**Project Name:** REDEVELOPMENT

**Project Number:** \_0335.00

**Schedule No. A-SC.04**

**Issue Date:** 07-July-2015

**Revision:** T02

- A) All ceiling lining are to be installed on ceiling batten unless noted otherwise.
- B) All painted ceiling surface are to be sealed and primed as per specification prior to carrying out finishes coat. All stopping and trowelling works are to be carried out to industry best practice. No Glancing light effect "variation in tone" are acceptable under all natural or artificial lighting conditions.
- C) Provide Skirting and ceiling cornice as per specification. If none specified builder is to allow for in the contract price the supply and installation of 100mm X19mm KDHW rectangular profile skirting with painted finish & square set finish to ceiling cornice with painted finish.

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	Special Notes
1	CF-01	Ceiling Finish	13mm Enviro Plasterboard		White		Generally except wet areas & playrooms	
2	CF-02	Ceiling Finish	13mm Boral Echostop 12mm Square Hole Perforated Plasterboard		White	Boral	Playrooms	
3	CF-03	Ceiling Finish	13mm Moisture Resistant Plasterboard		White	Boral or CSR	Wet Areas	

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	Special Notes
4	CF-04	Eave Soffit Finish	13mm Multiboard ILINE		White	Multiboard	External	
5	DANPALON	Danpalon 16mm To underside of Entry Canopy	Danpalon 16mm ICE		Ice	Danpalon	Entry Canopy	

# PROJECT SCHEDULE

## Door and Window Finishes

**TENDER ISSUE**

k20.AU PTY. LTD.  
t/a k20 ARCHITECTURE  
325 COVENTRY STREET  
SOUTH MELBOURNE 3205  
VICTORIA AUSTRALIA  
www.k20au.com  
t: 9699 4440  
f: 9699 5550  
e: melboffice@k20au.com



### IMPORTANT NOTE

All project schedules are to be read and co-ordinated with all other contract documents including project specifications prior commencement of any works, pricing, ordering and any other associated work. Any discrepancies are to be reported to the Superintendent for clarification. The Builder is to allow to supply and install all items within these schedules. For any item(s) noted in the project Drawings or Documentation which are not specifically indicated in the Project Schedules, the Builder is to provide for a commercial grade quality item to suit the documented item and provide a sample to the Superintendent for approval.

MARIBYRNONG RIVER CHILDCARE

**Project Name:** REDEVELOPMENT

**Project Number:** \_0335.00

**Schedule No. A-SC.05**

**Issue Date:** 07-July-2015

**Revision:** T02

- A) Refer to consultant documentation for any under cut required to door leafs and ventilation grilles.
- B) Painting to any door leaves are to all faces include top and bottom edge faces.
- C) Any glazing nominated to be frosted or opaque finish are to be confirmed and approved by the Architect prior.
- D) Refer specification for glazing type and finishes.
- E) Finishes of window hardware if non specified are to be to the approval of the Architects.
- F) Provide for proprietary door and window seals to surrounds of all doors and windows. Provide sample to Superintendent for approval

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	Special Notes
1		External Windows	Double Glazed Aluminium				External	
2		External Glazed Doors	Double Glazed Aluminium				Entry, Playrooms	
3		Internal Glazed Viewing Panels	Single Glazed				MCH Waiting, Entry Airlock, Playroom 5 & 6	
4		Internal Glazed Doors	Single Glazed				Entry Airlock, MCH Waiting	


Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	Special Notes
5		Internal Solid Doors with Viewing Panel	Dulux Paint Finish				Children's WC, Doors to Playroom 5 & 6	
6		Internal Solid Doors	Dulux Paint Finish				DDA WC, MCH 01 & 02	
7		External Solid Doors with Viewing Panel					External Doors to Children's WC	
8		Obscure window film to glazings to MCH Waiting						
9		Privacy Roller Blinds	Versilux with Mermet Revive Greenscreen. Non-transparent fabric.				To Windows of MCH 01 & 02	
10		Glazed Viewing Panel					As shown on drawings	
11	KP	Kick Plate to Doors					T.B.C.	
12		External Louvers to Playroom 5 clerestory awning windows					Playroom 5	

# PROJECT SCHEDULE

## Joinery

### TENDER ISSUE

k20.AU PTY. LTD.  
t/a k20 ARCHITECTURE  
325 COVENTRY STREET  
SOUTH MELBOURNE 3205  
VICTORIA AUSTRALIA  
www.k20au.com  
t: 9699 4440  
f: 9699 5550  
e: melboffice@k20au.com








#### IMPORTANT NOTE


All project schedules are to be read and co-ordinated with all other contract documents including project specifications prior commencement of any works, pricing, ordering and any other associated work. Any discrepancies are to be reported to the Superintendent for clarification. The Builder is to allow to supply and install all items within these schedules. For any item(s) noted in the project Drawings or Documentation which are not specifically indicated in the Project Schedules, the Builder is to provide for a commercial grade quality item to suit the documented item and provide a sample to the Superintendent for approval.

MARIBYRNONG RIVER CHILDCARE  
**Project Name:** REDEVELOPMENT  
**Project Number:** \_0335.00  
**Schedule No. A-SC.06**  
**Issue Date:** 07-July-2015  
**Revision:** T02

- A) Joinery finishes schedule to be read in conjunction with architectural documentation and project specification.
- B) Laminex E0 range (low emission board) to be used throughout, with 2mm ABS edging to match selected laminate colour unless noted otherwise.
- C) Builder to confirm actual dimensions on site prior to fabrication of joinery. Any discrepancies found on site is to be reported to the Architects immediately for clarification.
- D) Builder to co-ordinate the ordering of materials with sufficient lead time to ensure project program is not delayed.
- E) Builder to check dimensions of all equipment to be installed into joinery and confirm any adjustments to joinery dimensions to Superintendent for approval prior to manufacture.

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	Special Notes
1	LM01	Joinery Laminate Finish	Laminate		Sakkara Ivory Natural	Laminex	Benchtops	
2	LM02	Joinery Laminate Finish	Laminate		Parchment White	Laminex	Overhead cupboards, full height cupboards, office desks	

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	Special Notes
3	LM03	Joinery Laminate Finish	Laminate		Seasoned Oak	Laminex	Below bench cupboards & pram store, bag shelves	
4	LM-04	Joinery Kickboards	Laminex		Zincworks		Joinery kickboards	
5	SH	Shelves in Children's Store Rooms	Dexion long span 600D shelving		Dexion long span 600D shelving	Dexion	External Store	
6		Feature Display Cabinets	Custom made for size and finish		Back and all sides to unit shall be finished with Laminex 10mm thick compact laminate board in black, unit to be 200mm deep with sizing for height and width to each unit to vary. Glass to be toughened safety glass to display front. Aluminium 30mm thick frame to be powdercoat finished in selected colour. Refer Architectural Documentation for colour details.	Shop Front: <a href="http://www.showfront.com.au/display-cabinets/wall-mounted-display-cabinets/wmc-1200">http://www.showfront.com.au/display-cabinets/wall-mounted-display-cabinets/wmc-1200</a>	Entry Area	Feature Display Cabinets to be lockable
7	JP	Joinery Pull Handle	Madinoz by Dorma		MDZ 132 Satin Stainless Steel finish	<a href="http://www.madinoz.com.au/product/103">http://www.madinoz.com.au/product/103</a>		

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	Special Notes
8		Demolish existing joineries to Playroom 6 & prepare area for new joineries						
9	ST	Toy Storage Plastic Tub to MCh Waiting	Kis Bi Box Large 40L Container White 550W x 350D x 280Hmm				MCH Waiting	
10		Note: provide magnetic lock to all Playroom's & MCH 1 and 2 full height cupboards  Provide separate Master Key locks to all full height joineries in MCH Waiting, master key to existing building system					MCH Waiting	
11		Bench seating fabric	Interplay	 Agent	Active - Agent	<a href="http://www.instyle.com.au/new-products.htm#/products/products-by-name/by-textile-">http://www.instyle.com.au/new-products.htm#/products/products-by-name/by-textile-</a>	MCH Waiting	



# PROJECT SCHEDULE

## Fixtures & Fittings

### TENDER ISSUE

K20.AU PTY. LTD.  
t/a k20 ARCHITECTURE  
325 COVENTRY STREET  
SOUTH MELBOURNE 3205  
VICTORIA AUSTRALIA  
www.k20au.com  
t: 9699 4440  
f: 9699 5550  
e: melboffice@k20au.com



MARIBYRNONG RIVER CHILDCARE

**Project Name:** REDEVELOPMENT

**Project Number:** \_0335.00

**Schedule No. A-SC.07**

**Issue Date:** 07-July-2015






**Revision:** T02

#### IMPORTANT NOTE

All project schedules are to be read and co-ordinated with all other contract documents including project specifications prior commencement of any works, pricing, ordering and any other associated work. Any discrepancies are to be reported to the Superintendent for clarification. The Builder is to allow to supply and install all items within these schedules. For any item(s) noted in the project Drawings or Documentation which are not specifically indicated in the Project Schedules, the Builder is to provide for a commercial grade quality item to suit the documented item and provide a sample to the Superintendent for approval.



A) All new sanitary tap and shower water supply to be connected with to thermostatic mixing valves in accordance with Australian standards AS/NZS 00.4:1997. Should no thermostatic mixing valve be called up in the hydraulic documentation provide Enware Aquablend 1500 ATM700 mixing valve to project. Location of mixing valve to be mounted within a lockable flush mounted recessed wall panel, position to the Architects approval.

B) Allow to caulk all new junctions to fixtures and fittings where abutting a wall or floor, obtain approval from Superintendent on colour and type of caulking prior to installation

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	ESD/Special Notes	Rev
1	WC-01	ACCESSIBLE TOILET PAN	CAROMA		CARE 800 WALL FACED TOILET SUITE - with anthracites seat 320030AG - colour T.B.C	<a href="http://www.caroma.com.au/bathrooms/as1428-1-compliant/toilet-suites/care-800-wall-faced-toilet-suite">http://www.caroma.com.au/bathrooms/as1428-1-compliant/toilet-suites/care-800-wall-faced-toilet-suite</a>	ACC WC (1no.)	WELS 4 STAR	AS PER AS1428.1. ENSURE CONTRASTING TOILET SEAT TO SURROUNDING MATERIAL (30% MINIMUM CONTRAST REQUIRED TO SURROUNDING MATERIALS)
2	GR	TOILET GRAB RAIL & BACK REST	METLAM		MLR103/104	<a href="http://www.metlam.com.au/products/care/209">http://www.metlam.com.au/products/care/209</a>	ACC WC (1no.)		
3	WC-02	TOILET	CAROMA		JUNIOR 100 CONNECTOR SUITE S-TRAP STD SEAT #984241W	<a href="http://www.caroma.com.au/bathrooms/toilet-suites/junior/junior-100-connector-suite">http://www.caroma.com.au/bathrooms/toilet-suites/junior/junior-100-connector-suite</a>	Playroom 5 WC (2 no.)	WELS 4 STAR	Provide units to each children's toilet amenities as indicated on drawings.
4	TRH	TOILET ROLL HOLDER	METLAM		DOUBLE TOILET ROLL DISPENSER ML835	<a href="http://www.metlam.com.au/webdata/catalogue/Sect%201%20-%2008%20Toilet%20Roll%20Holders%20&amp;%20DispensersREV2.pdf#page=1">http://www.metlam.com.au/webdata/catalogue/Sect%201%20-%2008%20Toilet%20Roll%20Holders%20&amp;%20DispensersREV2.pdf#page=1</a>	Playroom 6 WC (2 no.) Playroom 5 WC (2 no.) ACC WC (1no.)		MOUNTING HEIGHT AS PER AS1428.1
5	HB-01	BASIN	CAROMA		CUBE WALL EXTENDED CODE NO 864115W 1TH	<a href="http://www.caroma.com.au/bathrooms/as1428-1-compliant/wall-basins/cube-care">http://www.caroma.com.au/bathrooms/as1428-1-compliant/wall-basins/cube-care</a>	ACC WC (1 no.),		Install AS PER AS1428.1

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	ESD/Special Notes	Rev
6	HB-02	BASIN	CAROMA		GRACE 565 VANITY BASIN	<a href="http://www.caroma.com.au/bathrooms/basins/grace/grace-565-vanity-basin">http://www.caroma.com.au/bathrooms/basins/grace/grace-565-vanity-basin</a>	MCH 01 (1 no.) MCH 02 (1 no.)		
7	BB	BABY BATH (with 1 no. Tap)	BRITEX		BB1 BABY BATH	<a href="http://www.britex.com.au/baby-bath">http://www.britex.com.au/baby-bath</a>	Playroom 5 WC (1 no.)		Provide Nappy Change Bench
8	BT	BASIN TRAP	CAROMA		Eco Blanc Bottle Trap 687295W	<a href="http://www.caroma.com.au/bathrooms/basins/bottletraps/eco-blanc-bottle-trap">http://www.caroma.com.au/bathrooms/basins/bottletraps/eco-blanc-bottle-trap</a>	ALL New WC		
9	TP-01	TAP	CAROMA		ACQUA CARE BASIN MIXER	<a href="http://www.caroma.com.au/bathrooms/mixer-taps/acqua/acqua-basin-mixer">http://www.caroma.com.au/bathrooms/mixer-taps/acqua/acqua-basin-mixer</a>	ACC WC (1no.)	WELS 5 STAR	Install AS PER AS1428.1
10	TP-02	MOTION SENSOR TAP (automatic with tapered water)	ZIP - Note Client supplied and installed through Council contract; Stuart Henderson, +61 424 750 855, Stuart.Henderson@zipindustries.com		ZIP DECK MOUNTED DIAGONAL MODELS 42208 AND 42211 BRUSHED STAINLESS STEEL	<a href="http://www.enware.com.au/store/ArticleDocuments/124/ENM6120_TDS.pdf.aspx?Embedded=Y">http://www.enware.com.au/store/ArticleDocuments/124/ENM6120_TDS.pdf.aspx?Embedded=Y</a>	MCH1 (1 no.) MCH2 (1 no.)		SENSOR TAP PROVIDE POWER
11	TP-03	TAP	CAROMA		CAROMA ACQUA SINK MIXER	<a href="http://www.clark.com.au/products/kitchen-taps/kitchen-mixer-taps/dorf-maximus-sink-mixer">http://www.clark.com.au/products/kitchen-taps/kitchen-mixer-taps/dorf-maximus-sink-mixer</a>	Playroom 6 (1 no.) Playroom 5 (2 no.)	WELS 5 STAR	Provide to each Art Sink. Position centrally to back side of sink
12	SNK-01	SINK	CLARK		Monaco Single End Bowl	<a href="http://www.clark.com.au/products/kitchen-sinks/monaco/monaco-single-end-bowl">http://www.clark.com.au/products/kitchen-sinks/monaco/monaco-single-end-bowl</a>	Playroom 6 (1 no.) Playroom 5 (2 no.)		

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	ESD/Special Notes	Rev
13	SNK-02	CHILDREN'S SINK	BRITEX		Pre-Plumbed Hand Wash Trough - TPWDPH 1200mm L x 400mm D, 3 no. TP04 to each sink	<a href="http://www.britex.com.au/pre-plumbed-hand-wash-trough">http://www.britex.com.au/pre-plumbed-hand-wash-trough</a>	Playroom 5 WC ,		Provide in 304 grade stainless steel supplied complete with Watermark certified grade 316 SS waste outlet (LSPW) - product code LBX. Confirm existing Joinery space dimensions prior to order to ensure fitting without clashes including to pull out steps under.
14	TP-04	Timed Flow Tap for Playroom 5 Children's Art Sink	Presto		Presto 704 Timed Flow Tap for Playroom 5 Children's Art Sink	<a href="http://www.thornthwaite.com.au/product-presto-704-timed-flow-tap.aspx">http://www.thornthwaite.com.au/product-presto-704-timed-flow-tap.aspx</a>	Playroom 5 WC (3no.) , Playroom 6 WC (3no.)		
15	CH	Clothes Hook	Concealed Fix Coat Hook with Circular Plywood Backing Plate			<a href="http://www.metlam.com.au/webdata/catalogue/Sect%201%20WASHROOM%20ACCESSORIES%20FINAL%205-10-2011.pdf#page=26">http://www.metlam.com.au/webdata/catalogue/Sect%201%20WASHROOM%20ACCESSORIES%20FINAL%205-10-2011.pdf#page=26</a>	ACC WC		INSTALL AS PER AS1428.1
16	SD-01	SOAP DISPENSER	JD MACDONALD		0327 STAINLESS STEEL 304	<a href="http://www.jdmacdonald.com.au/recessed-soap-dispenser-1/">http://www.jdmacdonald.com.au/recessed-soap-dispenser-1/</a>	ACC WC,		INSTALL AS PER AS1428.1, ABOVE HAND BASIN. Allow to key lockes to Council's Masterkey system.
17	SD-02	MANUAL FOAMING SOAP DISPENSER	KIMBERLY CLARK		AQUARIUS CODE 69480	<a href="http://www.kcprofessional.com.au/products/dispensers/skincare-dispensers/foam-soap-dispensers/69480-aquarius-hand-cleanser">http://www.kcprofessional.com.au/products/dispensers/skincare-dispensers/foam-soap-dispensers/69480-aquarius-hand-cleanser</a>	MCH 1 & 2		
18	PTD	PAPER TOWEL DISPENSER	METLAM		ML726W Paper Towel Dispenser - White Powder Coat		MCH 1 & 2		
19	SD-03	AUTOMATED SOAP DISPENSER	BRADLEY		BRADLEY AUSTRALIA 6120 AUTOMATIC SOAP DISPENSER	<a href="http://www.washroomaccessories.com.au/bradley-australia/2615-6120-sensor-operated-soap-dispenser.html#BRADLEY">http://www.washroomaccessories.com.au/bradley-australia/2615-6120-sensor-operated-soap-dispenser.html#BRADLEY</a>	Playroom 5 WC ( 2no.) Playroom 6 WC (2no.)	Bulkh refill soap dispenser	Provide 2no. Soap Dispensers to each Children's Wash Trough
20	HD	HAND DRYER	JD MACDONALD		AUTOBEAM WITH SILVER NOZZLE	<a href="http://www.jdmacdonald.com.au/autobeam/">http://www.jdmacdonald.com.au/autobeam/</a>	Playroom 5 & 6 WC, ACC WC		MOUNT NOZZLE AT 1000mm AFFL to ACC; mount at 800mm AFFL for children's WC


Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	ESD/Special Notes	Rev
21	MR	MIRROR	Viridian Optimirror				ALL WC		Refer to specification for details
22	BCS	WALL MOUNTED FOLD DOWN BABY CHANGE TABLE	JD MACDONALD		BCP-JDM: SURFACE MOUNTED PARALLEL CLASSIC BABY CHANGE STATION POLYETHYLENE	<a href="http://www.jdmacdonald.com.au/bcp-jdm-surface-mounted-parallel-classic-baby-change-station-polyethylene/">http://www.jdmacdonald.com.au/bcp-jdm-surface-mounted-parallel-classic-baby-change-station-polyethylene/</a>	ACC WC		Provide all necessary fixtures and fittings for a completed installed baby change folding table. Ensure secure fixing to wall with all necessary back blocking to stud wall
23	BIN	PULL OUT BIN	PULL OUT BIN		Deluxe KK12D (300W X 450H X 520D)	<a href="http://www.hideawaybins.com.au/gallery/online-gallery--hideaway-range-features.aspx">http://www.hideawaybins.com.au/gallery/online-gallery--hideaway-range-features.aspx</a>	Playroom 5 WC, Playroom 6 WC MCH 1 & 2		PROVIDE TO EACH NAPPY CHANGE JOINERY UNIT ,MCH 1 & 2 HANDWASH
24	FW	FLOOR WASTE							
25		CUSTOMIZED MAILBOX							
26		WC-EX	REUSED EXISTING WC						
27		TP-EX	RESUSED EXISTING TAP						
28		SNK-EX	REUSED EXISTING SINK						
29	BBM	BABY MEASURER	KAYENDEE		Standard Size: H 76mm (side) x W 500mm x D 1000mm Material: Clear Acrylic (Perspex) 6mm thick Base fitted with non-slip rubber pads		MCH 01, 02		

# PROJECT SCHEDULE

## Electric & Equipment

### TENDER ISSUE

k20.AU PTY. LTD.  
t/a k20 ARCHITECTURE  
325 COVENTRY STREET  
SOUTH MELBOURNE 3205  
VICTORIA AUSTRALIA  
www.k20au.com  
t: 9699 4440  
f: 9699 5550  
e: melboffice@k20au.com



MARIBYRNONG RIVER CHILDCARE

**Project Name:** REDEVELOPMENT

**Project Number:** \_0335.00

**Schedule No. A-SC.08**

**Issue Date:** 07-July-2015

**Revision:** T02

#### IMPORTANT NOTE

All project schedules are to be read and co-ordinated with all other contract documents including project specifications prior commencement of any works, pricing, ordering and any other associated work. Any discrepancies are to be reported to the Superintendent for clarification. The Builder is to allow to supply and install all items within these schedules. For any item(s) noted in the project Drawings or Documentation which are not specifically indicated in the Project Schedules, the Builder is to provide for a commercial grade quality item to suit the documented item and provide a sample to the Superintendent for approval.

- A) All lighting layout and positioning are to be confirmed with the Architects prior installation
- B) Any light switches and power points located externally are to be weatherproof IP rated to the Architects approval.
- C) A sample of specified light fittings are to be submitted to the Architects prior installation.
- D) All new powerpoints to be connected back to switchboard and allocated on separate circuits to suit equipment loading to areas
- E) All new data points are to be connected back to proposed server position, allow to fully patch into patch panel for connection, unless noted otherwise provide for minimum 20% spare capacity at patch panel for future connections
- F) All wiring to be concealed in wall and/or ceiling build ups, no exposed wiring unless noted specifically in documentation

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	Special Notes
1		LED Strip Lights to Back Light Signage to Street	LED Strip Lights		Warm White	<a href="http://www.laserlighting.com">www.laserlighting.com</a>	To Back Light Signage	LED STRIPS TO RUN LENGTH OF SIGNAGE BOTH TOP AND BOTTOM OF LETTERS. PROVIDE MOUNTING CLIPS FOR MOUNTING OF LED STRIPS SECURELY, ALLOW TO PAINT OUT BACKING MATERIAL BEHIND PERSPEX IN WHITE PAINT.

# PROJECT SCHEDULE

## Specialist Equipment

**TENDER ISSUE**

k20.AU PTY. LTD.  
 t/a k20 ARCHITECTURE  
 325 COVENTRY STREET  
 SOUTH MELBOURNE 3205  
 VICTORIA AUSTRALIA  
 www.k20au.com  
 t: 9699 4440  
 f: 9699 5550  
 e: melbooffice@k20au.com



**IMPORTANT NOTE**

All project schedules are to be read and co-ordinated with all other contract documents including project specifications prior commencement of any works, pricing, ordering and any other associated work. Any discrepancies are to be reported to the Superintendent for clarification. The Builder is to allow to supply and install all items within these schedules. For any item(s) noted in the project Drawings or Documentation which are not specifically indicated in the Project Schedules, the Builder is to provide a commercial grade quality item to suit the documented item and provide a sample to the Superintendent for approval.

**MARIBYRNONG RIVER CHILDCARE**  
**Project Name: REDEVELOPMENT**  
**Project Number: \_0335.00**  
**Schedule No. A-SC.09**  
**Issue Date: 07-July-2015**  
**Revision: T02**

- A)
- B)
- C)

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	Special Notes
1		Solatube skylights	Solamaster series 330 DS, provide daylight dimmer addon (530mm DIA)				Playroom 6 (3 no.)	Provide daylight dimmer addon (530mm DIA) flushing insulator, security bar, and all the necessary accessories for open and closed ceiling. Prismatic Diffuser.
2		Internal ceiling insulation	Batt type insulation		Recycled polyester insulation to achieve R 5.1		New Ceilings	
3		Internal wall insulation	Batt type insulation		Recycled polyester insulation to achieve R 3.0		New Walls	

Item	Code	Description	Product	Image	Colour / Model	Manufacturer / Contact	Location	Special Notes
7		Gas fired heating system (Space Heater) to Playroom 5 & 6					Children's Playroom 5 & 6	
8		Allow roof to Playroom 5 to connect to existing Rainwater Tank, provide pump						

# PROJECT SCHEDULE

Client Supplied Items fully Installed by Builder

**TENDER ISSUE**

k20.AU PTY. LTD.  
t/a k20 ARCHITECTURE  
325 COVENTRY STREET  
SOUTH MELBOURNE 3205  
VICTORIA AUSTRALIA  
www.k20au.com  
t: 9699 4440  
f: 9699 5550  
e: melboffice@k20au.com




## IMPORTANT NOTE

All project schedules are to be read and co-ordinated with all other contract documents including project specifications prior commencement of any works, pricing, ordering and any other associated work. Any discrepancies are to be reported to the Superintendent for clarification. The Builder is to install all items noted in this schedule allow to provide all necessary fixings and fittings for complete installations of each component.

MARIBYRNONG RIVER CHILDCARE  
**Project Name:** REDEVELOPMENT  
**Project Number:** \_0335.00  
**Schedule No. A-SC.09**  
**Issue Date:** 07-July-2015  
**Revision:** T02

- A)
- B)
- C)

Item	Code	Description	Product	Image	Colour / Model	Supplier / Contact	Location	Special Notes
1	TP-02	MOTION SENSOR TAP (automatic with tapered water)	ZIP - Note to be supplied and installed through Council contract; Stuart Henderson, +61 424 750 855, Stuart.Henderson@zipindustries.com		ZIP DECK MOUNTED DIAGONAL MODELS 42208 AND 42211 BRUSHED STAINLESS STEEL	<a href="http://www.enware.com.au/estore/ArticleDocuments/124/ENM6120_TDS.pdf.aspx?Embed=Y">http://www.enware.com.au/estore/ArticleDocuments/124/ENM6120_TDS.pdf.aspx?Embed=Y</a>	MCH1 (1 no.) MCH2 (1 no.)	SENSOR TAP PROVIDE POWER